BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/06/12-13 Date: 11.02.2013 Item No: 29

SCHEDULE-B

NAME OF WORK:Improvements Roads & drains at 7th cross and Surroundings of Bagalagunte in w No-14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **Sri M.PRASANNA KUMAR**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	346.86	70.0	Rupees Seventy Only
2	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	52.07	3800.0	Rupees Three Thousand Eight Hundred Only
3	Providing and laying in position plain cement concrete of design mix M20 with OPC cement @320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reafirmed-2008 machine mixed, concrete laid in layers not blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	108.46	4900.0	Rupees Four Thousand Nine Hundred Only
4	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design flaps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	48.81	6800.0	Rupees Six Thousand Eight Hundred Only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications	Sqm	919.2	230.0	Rupees Two Hundred Thirty Only

Signature of the Contractor

Executive Engineer

6	Supplying and fixing precast rainforced concec slab 10cm thick including cost of reinforcement as per design and drawing material cost transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	260.37	1550.0	Rupees One Thousand Five Hundred Fifty Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne, Km for Rs. 2.00/Km c) Add loading and unloading.	Cum	346.86	70.0	Rupees Seventy Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,